

TURNBO RANCH INCLUDED FEATURES



QUESTIONS?
GET FAST ANSWERS



- Level 1 Black GE® Appliances
- Level 1 Builder's Landscape Package
- Full Yard Bermuda Grass
- Full Yard Irrigation System
- One Tree (Type Per Builder)

- Community Mailbox System
- Bronze Address Plaque
- Electric Community
- HOA Dues: \$500 Per Year (Subject to Change)

The above standard features are included in most plans. Some plans, however, may not have all features. Stylecraft reserves the right to change features and specifications without notice. See on-site Sales Executive for details. ©2023 Stylecraft. Revised date: 4.18.24



STYLECRAFT INCLUDED FEATURES



**QUESTIONS?
GET FAST ANSWERS**

BUILDER PROGRAMS

- Meet the Builder meeting with superintendent and sales representative (not applicable on some inventory homes)
- Two homeowner meetings before closing (home orientation and confirmation tour)
- Professional Quality Assurance Program
- Home builder one-year warranty program with full-time, professional Warranty Department

ENERGY EFFICIENCY

- R-38 blown insulation in ceiling
- R-15 batt insulation in walls
- R-30 batt insulation in sloped ceiling
- GreenGuard Plygood® sheathing system with R value 1.5 on exterior walls
- Elevate® white vinyl, double pane insulated windows w/half screens and double locks
- Divided light windows on front (per plan)
- Lomanco® Turbine vent system
- Polyseal foam in all wall penetrations
- Radiant barrier decking (per location)
- Programmable thermostat
- 50 gal. high recovery water heater
- Standalone Fresh Air System
- Blower door/air duct tests

ELECTRICAL

- TV cable in all bedrooms & living spaces (per plan)
- Pre-wired for CAT-5 telephone (per plan, per region)
- Structured wiring box
- Pre-wired for garage door opener
- Copper wiring
- Kichler® brushed nickel or black light fixtures
- Kichler® ceiling fan in family room
- Pre-wire for ceiling fan in bedrooms
- LED disc lighting in kitchen

EXTERIOR + STRUCTURAL

- Engineered post-tension foundation
- 25-year 3-tab shingles
- 16" on-center studs, all walls
- Nisus Bora-Care® termite treatment
- Fully wrapped exterior walls
- James Hardie® cement fiberboard siding (per plan) w/ 30-year limited warranty
- Stone and/or brick (per plan)

EXTERIOR + STRUCTURAL (CONTINUED)

- Sidewalk from front door to driveway (approx. 42" wide, per plan)
- Half-Lite fiberglass rear door
- Fiberglass insulated entry door
- 6' wooden privacy fence and posts with gate (per lot)
- 5'x 5' Rear Concrete Patio (Unless Covered Porch Included)

SECURITY

- Schlage® Deadbolt locks on exterior doors
- Smoke/carbon monoxide detectors (per code)
- Flood lights at front and back of house

KITCHEN + BATH

- 30" upper wood cabinets (per plan)
- 9" stainless steel, under mount double sink w/ sprayer in kitchen
- GE® appliances: Range, Dishwasher, Vented Micro-Hood
- Disposal
- Delta® chrome faucets
- Chrome bath accessories
- Gentlemen's height wood cabinets/vanity in kitchen and all baths
- Cultured Marble vanity with rectangular under mount sinks in all baths
- 36" tall mirrors, width determined by length of the vanity (per plan)
- Walk-In shower with fiberglass walls and floor in primary bath

INTERIOR + FLOORING

- Granite countertops with straight edge in kitchen
- Interior walls and ceilings painted flat PPG® latex paint, 1 standard color
- 3-1/4" baseboards, painted
- Garage painted to match interior of home
- Metal stair balusters (if applicable)
- 2" door casings
- Two-panel interior doors
- Storage shelf above washer/dryer
- Shaw® Tile in utility (second floor)
- Level 1 Shaw® glue down vinyl wood plank in first floor living spaces, utility, kitchen, breakfast, foyer, dining, hallways, and all baths (per plan)
- Shaw® carpet in bedrooms, closets, and second floor living spaces (per plan)
- Built-in shelf system in closets (per plan)

The above standard features are included in most plans. Some plans, however, may not have all features. Stylecraft reserves the right to change features and specifications without notice. See on-site Sales Executive for details. ©2023 Stylecraft. Revised date: 4.18.24

